DBCT Master Plan 2019 Update Community Reference Group 6 June 2019



Master Plan 2018



Recap on last years Master Plan


Key Messages	 Flagged a change in sentiment and increased demand DBCT not fully contracted and significant contract 	Step	Likely Scope	Capacity (Mtpa)
	 DBCT not fully contracted and significant contract renewals were due Outlined changes in legislation "Sustainable Ports Act" 	Zone 4	Completion of row 8, vertical western wall, replacement of reclaimer RL2 with a new stacker reclaimer to suit the new row 8 configuration, a new through-load conveyor and a new stacker to the west of Row 8.	89
	 Outlined changes in AU which added significant time to feasibility phases of expansion planning Highlighted expansion beyond the existing footprint (9X) was unlikely 	8X	Stockyard Augmentation Project, rail receival pit 4 & inloading silos, possible upgrade to inloading 2 and outloading 2, stacker ST2 upgrade, Stacker ST1 replacement, upgrade of conveyors R1 and R2, and a new berth to the south.	Up to 102
	Expansion Pathway remained unchanged from MP16	9Х	New stockyard at Louisa Ck, upgrades to inloading 1(and inloading 2 if not done in 8X), new outloading system 4 and up to 2 berths to the north	Up to 136

What has changed in 2019?



Contracted Capacity

- After a period of several years where some capacity had been relinquished DBCT is now almost fully contracted again with only some near term capacity available.
- Recent Access Applications indicate demand for additional capacity




What has changed in 2019?



Contracted v's Throughput

- Throughput hasn't changed much since 2014
- Gap between Contract and Throughput expected to close over the next couple of years
- Many of the terminal assets are over 35 years old and this older equipment will be expected to be reach unprecedented levels of availability
- Significant issue looming with shiploader availability in particular

5 Year Capacity v's Throughput Outlook



New expansion step introduced



Shiploader SL4 on Berth 3

- Benefits SL4 provides additional System Capacity by increasing Outloader availability – Up 4.3Mtpa to 88.5Mtpa
 - Lowest cost expansion available to DBCT
 - Quicker than Zone 4 to implement
 - SL4 on Berth 3 is the first expansion proposed in Master Plan 2019





- **Zone 4** Zone 4 was the first expansion in the last 2 Master Plan revisions
 - Scope is still identical
 - Some of the benefit will be delivered by SL4 but the cost is the same making it less attractive commercially
- ST1 replacement was in proposed scope of 8X Phase 1 but that replacement is already underway therefore making this project more attractive than Zone 4 as the next step after SL4
- Capacity modelling of Inloading Silos indicate benefit is marginal capital and maintenance cost is high, therefore deleted from MP2019
 - More conveyor connections added from proposed new inloading conveyors to existing stockyard to compensate for Silos not being included
 - With Silos deleted, 8X Phase 2 is more commercially attractive than Zone 4 after 8X Phase 1
 - Still included in MP2019 but this project is still difficult

9X

Revised Expansion Pathway Master Plan 2019



Step		Scope	Incremental Capacity	Capacity (Mtpa)
Within Footprint	Shiploader 4 on Berth 3	The provision of a 4 th Shiploader on Berth 3 plus outloading debottlenecking	4.3	88.5
	8X Phase 1	Stockyard Augmentation Project (SAP) plus upgrade of Stacker ST2 and conveyors S5, S6A, S6, R1 and R2	2.7	91.2
	8X Phase 2	Rail Receival pit 4 & Inloading System 4 plus upgrade to Inloading 2 and Outloading 2	3.3	94.5
	Zone 4	Completion of row 8, vertical western wall, replacement of reclaimer RL2 with a new Stacker Reclaimer to suit the new row 8 configuration, a new stacking conveyor and a new Stacker to the west of Row 8.	3.0	97.5
New Stockyard	9X	New Stockyard at Louisa Ck, Upgrades to Inloading 1 (and Inloading 2 if not done in 8X), new Outloading System 4 and up to 2 berths to the north including significant land reclamation to accommodate dredge spoil	≈34	131

Expansion Scope – 4 Expansion Steps to achieve maximum capacity for existing footprint





Expansion Scope – Expansion Beyond the footprint is more difficult





Difficulties include:

- Community impact
- Significant delays for dredging approvals meaning material spend before any certainty of approvals
- Asset Stranding risk of differentially priced expansion

9X - Louisa Ck

Dredge Spoil Reclamation





QUESTIONS